

| SI No | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Unit | No | L     | B | D | Qty   | Rate    | Amount  |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----|-------|---|---|-------|---------|---------|
| 11    | Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., P No. 44 / I No. 6.6.6 KPWD Electrical SR 2014-15                                                                                                                                                                                                                                                                                                                         | Each |    |       |   |   |       |         |         |
| 12    | Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A P No. 55/ I No. 7.4.4 4 core 16 Sqmm KPWD Electrical SR 2014-15                                                                                                                                                                                                                | Mtr  | 2  |       |   |   | 2     | 302.00  | 604.00  |
| 13    | Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. In existing trench/duct. P No. 61 / I No. 7.8.1 6Sqmm to 16 Sqmm) KPWD Electrical SR 2014-15                                                                                                                                                                                                                                                                                                                                                                                         | Mtr  | 2  | 30.00 |   |   | 60.00 | 140.40  | 8424.00 |
| 14    | Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete. (As per Civil SR KSRB I-2, P-7) P No. 61 / I. No. 7.9.3 KPWD Electrical SR 2014-15                                                                                                                                                                                                                                                                                                                                                                                                | Mtr  | 2  | 30.00 |   |   | 60.00 | 10.80   | 648.00  |
|       | For Cutting Road Surface                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |      |    |       |   |   |       |         |         |
| 15    | Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV P. No. 62 / I No. 7.12.1 KPWD Electrical SR 2014-15                                                                                                                                                                                                                                                                                                                                                                             | Mtr  | 2  | 25.00 |   |   | 50.00 | 85.00   | 4250.00 |
|       | 40mm dia GI pipe                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |      |    |       |   |   |       |         |         |
| 16    | Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P. No. 62 / I.No. 7.13.2 KPWD Electrical SR 2014-15                                                                                                                                                                                                                                                                                                                                                                | No.  | 2  | 4.00  |   |   | 8.00  | 345.00  | 2760.00 |
|       | 16Sqmm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |    |       |   |   |       |         |         |
| 17    | Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia, (P No. 55, I No. 7.1) KPWD Electrical SR 2014-15 | No   | 2  |       |   |   | 2.00  | 280.00  | 560.00  |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |    |       |   |   |       |         |         |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      | 2  |       |   |   | 2     | 2727.00 | 5454.00 |